

MASTER CONSTRUCTION
P. O. BOX 226984 · DALLAS, TEXAS 75222-6984
(214) 748-5611 · FAX (214) 748-8577

Bid Submitted To:

Name:	Robert Bauer	Job:	Pavement Budget Numbers
Street:	1950 Wilshire	Street:	Wilshire to Brentwood
City:	Irving TX	City:	Irving TX
Contact:	Robert Bauer	Phone #:	972-322-1600
Date:	5/18/2009	Fax #:	
Email:		Cell:	

REMOVE THE EXISTING PAVING AND REPLACE WITH NEW CONCRETE PAVING (64,000 SF)

Remove the existing concrete paving ½ at a time. Compact the sub-grade with 2" of flex base and reinforce with #3 rebar 18" on center attached to existing concrete surfaces with dowels. Place 6" of 3500PSI concrete.

Budget Price: \$ 486,767.29
Payment Terms: Net 10 Days

REMOVE THE EXISTING PAVING AND REPLACE WITH 1 ½ " OF TYPE D ASPHALT (64,000 SF)

Apply tack and lay Hot tpe D asphalt 1 ½" thick and compact with a rubber tire and steel wheel rollers.

Budget Price: \$66,989.00
Payment Terms: Net 10 Days

SEAL THE EXISTING CRACKS

Rout the existing cracks and fill with WR Meadows Hot pour crack fill.
Budget Price: \$1.50 per lineal foot

Excludes permits, permit drawings, inspection fees damage to underground utilities and lab fees.

Thank you for the opportunity to quote this project, tax is not included in the price.
Jim Coulter
jimc@masterconstruction.com